BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41600

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Emergency Works like Desilting of drains, Constructions of Culvets etc, in Ward No 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRITHVISAGAR K ( )	
				In Figures	In Words
1	15	1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XLVIII / I. 23) PWD SR 2018-19	Day	4840.75	Rupees Four Thousand Eight Hundred Forty and Seventy Five Paise Only
2	75	1024 - Hire Charges of Tractor 50 HP including Operator and Fuel (P. XLVIII/I. 20) PWD SR 2018-19	Day	1809.65	Rupees One Thousand Eight Hundred Nine and Sixty Five Paise Only
3	750	Engaging Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2018-19 Page No. LVI/SL NO. 5)	Nos	379.27	Rupees Three Hundred Seventy Nine and Twenty Seven Paise Only
4	30.24	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	117.13	Rupees One Hundred Seventeen and Thirteen Paise Only
5	3.89	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 13/ Item No. 4.3/ PWD SR 2018-19	Cum	4596.9	Rupees Four Thousand Five Hundred Ninety Six and Ninety Paise Only
6	12.96	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 25/ Item No. 5.9/ PWD SR 2018-19	Sqm	4940.18	Rupees Four Thousand Nine Hundred Forty and Eighteen Paise Only
7	3.24	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	4783.41	Rupees Four Thousand Seven Hundred Eighty Three and Forty One Paise Only
8	21.6	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm	190.11	Rupees One Hundred Ninety and Eleven Paise Only
9	18	Providing precast slab of 250mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	4605.3	Rupees Four Thousand Six Hundred Five and Thirty Paise Only
10	37.8	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	1986.45	Rupees One Thousand Nine Hundred Eighty Six and Forty Five Paise Only

Prithvi Sagar. K.

Signature of the contractor

20/06

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRITHVISAGAR ( )	
				In Figures	In Words
11	30.24	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	51.36	Rupees Fifty One and Thirty Six Paise Only

Prithvi Sagar K.

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

20/06

20/06